

Tift County High School Performing Arts Center Technical Specifications

DIMENSION INFORMATION

STAGE DIMENSIONS

Proscenium	Width 60' 5" Height 20' 9 ½"
Proscenium to Apron	9' 2 ½" at center point
Stage Extension Width Orchestra pit.....	8' 7 ½"
Curtain line to back wall Depth.....	40'
Curtain line to last line	29' 6"
First line to last line.....	21'-6"
Distance from edge of stage to Act Curtain line at center (including 8' 7' ½" pit cover)	17" 10"
Stage Center to SL fly gallery	24' 8"
Stage Center to SR fly gallery.....	25' 2"
Wing space SL	18' 2"
Wing space SR.....	18' 2"
Backstage crossover width	11' 4"

Stage Floor (including wing space): Hardwood maple parkay flooring over poured concrete.

There are no trap doors or stage crossovers. Please no nailing or screwing into the stage floor.

LOADING DOCK

Loading doors.....	8'w x 10'h.
Dock height from street level	16"
Outside, stage level, off upstage right. Will accommodate one tractor trailer.	

Trailer will need to be dropped, and truck can be parked in rear of Faculty Lot during school days or Student Lot at discretion of Facilities Coordinator.

SOFT GOODS

2 pair black legs..... 18' wide x 21' high

2 black borders..... 70' wide x 5' high

See Hanging Plot

Act Curtain horizontal opening (manual SL), also mid and back travelers (manual SL)

FLY SYSTEMS

See hanging plot for details

Type..... Electric Wench

Weight..... 1200 lbs

Batten Lengths 65'

Length of wing battens 32' 10"

Fly Height 42'

low point 5' off stage

floor for electrics, all others dead hung.

HANGING PLOT

Ref	Name	Type of Rigging	Position behind Plaster Line
1	Valance	Dead Hung	0' 5"
2	Act Curtain	Dead Hung/Manual Open	1' 0"
3	Electric 1	Line Shaft Winch	2' 6"
4	Retractable A/V Screen	Dead Hung	4' 0"
5	Border 1	Dead Hung	4' 6"
6	Legs 1	Dead Hung	5' 6"
7	Electric 2	Line Shaft Winch	6' 6"
8	Border 2	Dead Hung	10' 6"
9	Mid-stage Traveler	Dead Hung/Manual Operation	11' 6"
10	Utility Batten	Dead Hung	12' 6"
11	Utility Batten	Dead Hung	13' 6"
12	Border 3	Dead Hung	14' 6"
13	Legs 2	Dead Hung	16' 0"
14	Electric 3	Line Shaft Winch	18' 0"
15	Utility Batten	Dead Hung	21' 0"
16	Rear Traveler	Dead Hung/Manual Operation	22' 0"